Note:

It takes min. 10 gallons of water to fully flush-out air from the system.

After installation, flush water filter at least 3 times to remove air from inside your new filtration system. Please do not drink this water.

Please fill the tank with water, is takes about 1.5 Hours and release water completely from storage tank, by opening fully filter faucet. Water should run for about 3-5 minutes.

Clouse filter faucet and wait again 1.5 hours. Release filtered water from tank. In first 3-5 days air will continue to be pushed out from the system. In the first days of use, water may have "milky" appearance. This is only air, in form of small babbles.

At this time water it safe to drink.

After 5 to 10 days air babbles should stop its appearance.

This new water system will produce up to 50 gallons per day (24 hr's) of purified alkaline and ionized water.